



NOTES:

1. ALL WOOD MATERIAL MUST BE NEW PRESSURE TREATED. PAINTED SURFACES ARE NOT ACCEPTABLE.
2. THE CONTRACTOR SHALL GROUND THE SERVICE FACILITIES. THE CONTRACTOR SHALL DRIVE THE GROUND ROD(S) ON METER SIDE OF PEDESTAL TO AVOID COMPANY CABLES.
3. THIS INSTALLATION IS AN ALTERNATE FOR MOBILE HOME PARKS AND MOBILE HOMES THAT ARE NOT APPROVED FOR THE INSTALLATION OF A METER ON THE SIDE.

200 A METER FITTING
 FREE STANDING – UNDERGROUND INSTALLATION
 120/240 VOLT, 1 PHASE, 3 WIRE
 120/240 VOLT, 3 PHASE, 4 WIRE
 225 A MAXIMUM SERVICE
 120/208 VOLT, 3 PHASE, 4 WIRE
 200 A MAXIMUM SERVICE



Freestanding
 Underground Riser